



# COMPANY INTRODUCTION

## **SOUTHERN ROCK CONTRACTING EST. (SRC)**

Southern Rock Contracting Est. (SRC) is an established industrial maintenance contractor with strong experience in executing high-risk works inside live operating plants, including:

- Fabrication – Assembly & Coating
- Site Installation, Shut down Works & Dismantling
- Shutdown & Turnaround Activities
- Piping Fabrication, Testing & Coating
- Complete Project Material and Consumable Trading
- Precision Machining, Turning & Milling.

Our Engineering services encompass design, detailing, reverse engineering, Controlled Dismantling and Demolition and technical consultancy, ensuring that every project is executed with precision and innovation.

# PAST DEMOLITION PROJECTS

NO	REGION	NAME OF PROJECT	WORK TRADE	UNIT
1	KSA	MAADEN BAUXITE & ALUMINIUM CO (MBAC) RASAL KHAIR	DEMOLITION OF RESIDUE STORAGE AREA 3	REFINERY
2	KSA	SABIC - KEMYA	CEMENT LINED PIPE REPLACEMENT IN LLDPE PLANT	REFINERY
3	KSA	SAUDI ARABIAN MINING COMPANY (MAADEN)	GAP AND LPT CIVIL WORKS AND ERECTION WORKS	REFINERY
4	KSA	SAUDI WATER PARTNERSHIP COMPANY (SWPC) SHUQAIQ	SHUQAIQ 3 SEA WATER RESERVE	WATER TREATMENT PLANT
5	KSA	JUBAIL UNITED PETROCHEMICALS (JUPEC)	DEMOLITION OF ETHLINE PLANT (UNIT 7-8)	PETRO CHEMICALS
6	KSA	KJO GLOBAL GAS AND NGL RECOVER HANDLING KAFJI	DEMOLITION OF EXISTING TANKS PLATFORM, FOUNDATION	REFINERY
7	KSA	SHOAIBA POWER AND DESALINATION PLANT - SAMSUNG ENGINEERING	DEMOLITION OF EXISTING HEAVY STEEL STRUCTURES	WATER DISTILLATION
8	KSA	AMERICAN AIR BASE	DEMOLITION OF REVETMENT MILITARY INSTALLATIONS	3 UNITS



# **CONTROLLED DEMOLITION of Damaged Nitrogen Receiver (T76-D-0041B)**

**BY  
SOUTHERN ROCK GROUP**

# CURRENT CONDITION

- Top ~9 m missing Remaining 15 m leaning on pipe rack.
- Heavy deformation at 6 m height
- Steel confirmed brittle due to LN<sub>2</sub> exposure  
Objective:
- To dismantle and remove the vessel safely without affecting the pipe rack or nearby assets.

# KEY CHALLENGES

- Brittle / glass-like steel behavior
- 30-ton leaning structure
- Stored energy at bent section
- Proximity to pipe rack & Vessel A
- Risk of shrapnel and sudden collapse
- Unknown residual LN<sub>2</sub> pockets

# **HAZARD IDENTIFICATION & CONTROLS**

## **MAJOR HAZARDS**

- **Brittle fracture**
- **Stored energy release**
- **Structural collapse**
- **Steam explosion during hot work**
- **Flying fragments**

## **CONTROLS**

- **30 m exclusion zone**
- **Hydraulic shear (primary method)**
- **Sandbag stabilization**
- **Cold tapping & O<sub>2</sub> monitoring**
- **Excavator Lexan windshield**
- **Crane slack-tension support**

# **SAFETY ZONES & PPE**

## **EXCLUSION ZONES:**

- 30 m radius during cutting
- 60 m × 40 m barricaded demolition area

## **PPE Requirements:**

- Full PPE + face shield
- FR clothing
- Polycarbonate windshield cab
- Long-distance tag lines
- No personnel under suspended load

# ATMOSPHERIC SAFETY

## **COLD TAP VERIFICATION:**

- 5 mm holes at 0 m & 6 m
- Confirm no pressure / LN<sub>2</sub> release
- O<sub>2</sub> > 19.5% before work

## **PURPOSE:**

- Prevent sudden nitrogen discharge and confirm no trapped cold pockets.

# **Site Preparation & Stabilization**

- **Remove loose debris using telehandler**
- **Protect ground using sand cushioning**
- **Install temporary supports**
- **Ensure 360° barricade**
- **Engineering survey for trapped energy**
- **Confirm mechanical & electrical isolation**

# **SANDBAG STABILIZATION SYSTEM**

## **PURPOSE:**

- Support vessel weight
- Absorb brittle fracture energy
- Protect pipe rack

## **SYSTEM:**

- 275+ Jumbo sandbags
- 5–6 m high pyramid
- Hand-packed small bags to fill gaps
- Curved cradle matching shell diameter

P. NORTH



N2 RECEIVER - B

N2 RECEIVER - A

EXCAVATOR WITH  
ORANGE-PEEL GRAB &  
HYDRAULIC CUTTER


BALLAST BASED  
FENCE POST

TEMPORARY SUPPORTS  
Super Sand Sacks (large 1-ton  
geotextile bags)

PROTECTIVE SAND CUSHION  
FOR FLOOR PROTECTION

DEMOLITION AREA  
BARRICADE, WARINING SINAGE

2 LAYER DEBRIS NETTING



# **PRE-DEMOLITION VERIFICATION**

- **Cold tap test**
- **O<sub>2</sub> monitoring >19.5%**
- **Strike test demonstration (brittleness)**
- **Team risk briefing**
- **Confirm no vibration transfer to pipe rack**

# **DISMANTLING STRATEGY**

## **PRIMARY METHOD:**

- **Excavator-mounted hydraulic shear**
- **Vertical “banana peel” cuts**
- **Stress-relief stripping**

## **SUPPORT METHOD:**

- **100T crane with 10–15% slack tension Sandbag energy absorption**
- **No manual intervention close to the vessel**

# **PHASE III: CUTTING SEQUENCE**

## **STEP 1 —**

- Crane Pre-Positioning
- Wire ropes only
- Slack-tension mode

## **STEP 2 —**


- Banana Peeling
- Vertical cuts
- Long strips remove hoop strength

## **STEP 3 —**

- Upper Section Removal
- Remove top 5 m first
- Crane lowers strips to safe area

# **CUTTING THE 6M BENT SECTION**

- **Most critical stage**
- **Top weight already removed**
- **Controlled cut above sandbag saddle**
- **Sandbags absorb drop**
- **Crane prevents roll-over**
- **Controlled redirection away from pipe rack**




# **CONTINGENCY**

## **Hot Work Plan B (If Shear Fails)**

- Conditions for Hot Work: Only when shear cannot penetrate

### **Plan**

- Preheat to 100–150°C
- Stitch cutting (30 cm cut / 20 cm bridge)
- Long torches (1.5–2 m)
- Fire blankets on sandbags
- Fire watch mandatory



# **VESSEL A PROTECTION PLAN**

## **Why Protection Is Required:**

- Vessel A already damaged
- 12 m from demolition site

## **Protection Measures:**

- Rubber blasting mats
- Jumbo sandbag vertical buffer
- Dedicated proximity spotter
- No equipment parking in 12-m zone
- Tail swing monitored

# **VIBRATION & CRACK** **MONITORING**

- **Restrictions on heavy shearing force**
- **If vibration impacts pipe rack → switch to stitch cutting**
- **Crack growth monitoring on Vessel A**  
**Immediate stop if new cracks observed**

# **DETAILED EXECUTION STEPS**

**Step 1:** Stabilization & sandbag positioning

**Step 2:** Remove loose sections


**Step 3:** Controlled removal of leaning upper section

**Step 4:** Peeling of main shell courses

**Step 5:** Skirt demolition

**Step 6:** Base ring removal

**Step 7:** Scrap segregation & cleanup



# EQUIPMENT PLAN

- Excavator with hydraulic shear & grab
- 100T mobile crane
- Manlift
- Telehandler
- Forklifts
- Cutting set (oxy-acetylene)
- Fire safety equipment
- Flatbed trucks & skip containers



# **MANPOWER PLAN**

- Project Manager
- Structural Engineer
- HSE Officer
- Crane operator
- Excavator operator
- Riggers (Level 1 & 2)
- Fire watch
- Scaffolders (as required)
- Helpers
- Shifts:12hr/ Day + 12hr Night Duration: 2–3 weeks

# **HSE MANAGEMENT**

- **No man-entry into collapse zone**
- **No welding lifting lugs**
- **Minimum hot work**
- **Continuous monitoring for shifts & cracking**
- **PTW compliance**
- **Emergency response readiness**

# **QUALITY ASSURANCE**

- **Inspection after each cut**
- **Record brittle behavior**
- **Ensure compliance with Method Statement**
- **Scrap quantity tracking**
- **Daily checklists & supervisor sign-off**

# **ENVIRONMENTAL PROTECTION**

- **Water spray for dust**
- **Noise control**
- **Proper waste segregation**
- **No contamination to surrounding area**

# CLIENT Q&A SUMMARY

1. Why sandbags instead of steel supports?

Sandbags absorb impact, distribute load, and prevent brittle cracking. Steel supports create dangerous point-loads.

2. Why treat the vessel as brittle after collapse?

LN<sub>2</sub> exposure permanently damages steel grain structure. The brittleness remains even at ambient temperature.

3. Why use hydraulic shear instead of torch cutting?

Cold cutting avoids thermal shock, keeps operator at a distance, and prevents sudden fracture.

# **CLIENT Q&A SUMMARY**

## **4. How is the pipe rack protected?**

**Weight reduction + sandbag buffer + controlled cutting direction away from the rack.**

## **5. Any nitrogen trapped?**

**Cold tap at 0m and 6m confirms safe O<sub>2</sub> (>19.5%) and releases pockets before work.**

## **6. What if the vessel suddenly shatters?**

**Exclusion zone, sandbag pyramid, and excavator Lexan shielding control the risk.**

# CLIENT Q&A SUMMARY

**7. Why is the crane used in slack-tension only?**

To catch movement without pulling on brittle steel, avoiding collapse.

**8. Why vertical “banana peel” cuts?**

They release internal stress slowly and prevent explosive shell failure.

**9. How is Vessel A protected?**

Rubber shields + sandbag barrier + no equipment entering the 12 m high-risk corridor.

# CLIENT Q&A SUMMARY

**10. What prevents sympathetic damage to nearby equipment?**

Controlled cutting direction, sand cushion, debris shielding, and strict proximity control.

**11. Why minimal hot work?**

Heat can trigger thermal cracking. Used only if shear fails.

**12. How long will the demolition take?**

Approx. 2–3 weeks, depending on debris and weather.

**13. What is the biggest risk?**

Brittle fracture and stored energy at the 6 m bend.

**14. How is that risk controlled?**

Stress-relief cuts, sandbag cradle, slack crane tension, exclusion zone.

## **CLIENT Q&A SUMMARY**

**15. Why no man-entry?**

The vessel is unstable; internal collapse risk is high.

**16. Why use telehandler for sandbags?**

Safer placement, no manual handling near risk zone.

**17. Why debris netting and plywood shielding?**

To catch small shrapnel and protect adjacent assets.

## CLIENT Q&A SUMMARY

**18. Why not use scaffolding for support?**

Steel supports can puncture brittle steel and trigger cracking.

**19. Why stitch-cutting during hot work?**

Prevents sudden drop—only small sections release at a time.

**20. What ensures quality compliance?**

Daily inspections, cut verification, and adherence to Aramco JSA/PTW.

# **CONCLUSION**

- **This demolition plan:**
- **Ensures full personnel safety**
- **Protects pipe rack & Vessel A**
- **Uses engineered controls**
- **Minimizes hot work**
- **Complies with Aramco standards**
- **Provides safe, efficient 2–3-week execution**